






NOTES			
1.	MARK OUTLINE OF PATCH USING STRAIGHT EDGE AS DEFINED ON SITE BY THE ENGINEER.		
2.	SAW-CUT ALONG OUTLINE OF PATCH TO DEPTH OF SURFACE COURSE. NOT LESS THAN 40 MM, SAW-CUT TO BE VERTICAL.		
3.	FOLLOWING EXCAVATION, ALL LOOSE MATERIAL TO BE REMOVED.		
4.	IN THE EVENT OF PATCHING BELOW BINDER COURSE LEVEL, EXCAVATION TO BE STEPPED BY A MIN OF 75 MM.		
5.	EXCAVATION TO BE OF A REGULAR DEPTH, VERTICAL EDGES OF EXCAVATION IN SURFACE COURSE AND / OR BINDER COURSE TO HAVE APPLIED APPROVED SEALANT TO FULL DEPTH OF JOINT IMMEDIATELY BEFORE PATCHING MATERIAL IS PLACED.		
7.	FILLING OF EXCAVATION TO BE CARRIED OUT IN THE FOLLOWING WAY:- A) MATERIAL TO BE PLACED FROM EDGES INWARDS, ARRISSES TO BE WELL COMPACTED. B) LAYER THICKNESS TO BE NO LESS THAN 1.5 TIMES NOMINAL AGGREGATE SIZE AND NO MORE THAN 2.5 TIMES NOMINAL AGGREGATE SIZE. C) MATERIAL TO BE COMPACTED TO REFUSAL USING MECHANICAL MEANS IN ACCORDANCE WITH THE SPECIFICATION (SEE APPENDIX 7/1).		
8.	IMMEDIATELY PRIOR TO PLACING OF SURFACE COURSE, LOOSE MATERIAL SHALL BE REMOVED FROM THE PATCH AND SURROUNDING AREA.		
9.	MATERIAL TO BE CONTAINED TO AVOID CONTAMINATION, SEGREGATION AND MAINTAIN UNIFORMITY OF TEMPERATURE (E.G. INSULATED BODY WITH APPROPRIATE COVER).		
10.	JOINT SEALANT TO BE APPLIED IF TRAFFIC HAS OVER-RUN THE EDGES OF PATCH OR TRENCH. IF PRE-COATED CHIPPINGS ARE TO BE USED THEY ARE TO BE FREE FROM CONTAMINATION.		
12.	COMPACT ALL EDGES FIRST USING APPROVED PLANT FOR COMPACTION AND BY WORKING INWARDS FROM EDGES.		
13.	COMPACTION TO BE CARRIED OUT TO REFUSAL. PATCH OR TRENCH TO BE LAYED IN EVEN LAYERS AND FOLLOW THE SHAPE OF THE ROAD.		
15.	SURFACE LEVEL TOLERANCES MUST BE WITHIN 0 MM TO +10 MM (MAXIMUM) AND NEVER BE LOWER THAN THE ADJACENT SURFACE LEVEL.		
16.	ALL DIMENSIONS ARE IN MILLIMETRES.		

**Walsall Council**

**Sandwell**
Metropolitan Borough Council

**Wolverhampton City Council**

**Regeneration and Transportation**

**Dudley**
Metropolitan Borough Council

FRAMEWORK CONTRACT FOR HIGHWAY WORKS - MINOR WORKS CONTRACT

Drawing Title:
PATCHING AND TRENCH REINSTATEMENTS

DRAWN	MJD	DATE	JUL/09
CHECKED	JBF	SCALE	1 : 25
Drawing Number	SD/700/06		
Rev	01		